

PART 3 -EXECUTION

3.01 INSPECTION:

- A. Opening Size: Verify opening size to be equal to that recommended for product by Chicago Bullet Proof Systems.
- B. Fit: Verify flatness/plumb and levelness of surfaces.

3.02 STORAGE:

- A. It shall be the responsibility of the general contractor to see that any scratches or disfigurement caused in shipping or handling are promptly cleaned and touched up with a rust-inhibitive primer (for painted surfaces), and that materials are properly stored on planks or dunnage, in a dry location, and covered to protect them from damage. Nothing shall be stored on top of any bullet resistant equipment.
- B. Windows and transparent armor shall be stored in an upright position.

3.03 INSTALLATION: Install work of this section according to manufacturer's recommendations, installation instructions and approved submittals. Install frames plumb, rigid and in true alignment. Utilize temporary supports for frames installed prior to wall erection. Install glass armor with the specified rubber spacers only for seating and securing glass in the frames. Calk frames where necessary (vision windows only). Glazing shall occur after all masonry, ceiling, electrical, plumbing and/or finish painting have been accomplished in order not to damage the bullet resistant transparent armor.

3.03 ADJUSTING and CLEANING: Leave glass clean according to manufacturer's recommendations and free of lables. Leave shop primed surfaces clean and ready for finish paint.